

From: Cisco Brink, Project Manager – RCCEDC

Date: October 13, 2023

Subject: PRO Bunny Hill – Utility Information

1. The following summary outlines requested information regarding the electricity requirement for PRO Bunny Hill.
2. Roswell's electric provider, Xcel Energy, reports that the proposed WETCO site currently has 4.5MW capacity. There is a 12.47 kV distribution line nearby and 2 transmission lines: a 69 kV line running along east side and a 115 kV line running along north side. The nearest substation is ¼ mile north of site. Upon request for service, the utility will work with the customer to determine the service type and begin the process to serve the short term load and install the infrastructure required to serve the customer's ultimate capacity needs.
3. Xcel Energy's current mix is 48 percent renewable (46% wind, 2% solar).
4. Xcel Energy's large general rates are available at the following link:  
[Rate 34, Rev. 9 - Large General Service - Transmission \(2-26-2022\).pdf \(xcelenergy.com\)](#)
5. The point of contact for this memorandum is Cisco Brink, RCCEDC Project Manager, at [cisco@chavescounty.net](mailto:cisco@chavescounty.net) or 575-500-2094.